

Address:

---

## **FIRE SAFETY PROCEDURES**

### **SITE FIRE PROTECTION**

Fire protection and supervision is the responsibility of the General Contractor, Any deficiencies to be reported to the general contractor.

### **SITE FOREMAN DUTIES**

- Site foreman to show all sub trade workers fire exit routes and review fire safety procedures
- Site foreman to identify gathering location for sub trade workers off site in the event of a fire or emergency
- Site foreman to keep track of all sub trade workers on site
- Site foreman to incorporate fire procedures into safety meetings
- Site foreman to ensure that combustible materials (e.g. cardboard boxes etc.) are removed from site, Site foreman is to ensure access to construction site at all times for Fire Dept. for fire fighting
- Site foreman is to ensure access to hydrant and water supply locations at all times

### **FIRE AVOIDANCE**

- All combustible material belonging to sub trades to be removed from site daily
  - Any soldering to be done with fire extinguisher on hand, *and* asbestos protection mat
  - Fire exits to be kept clear of any obstructions
  - Vehicles to be parked away from entry and fire hydrants
- Confirm that adequate fire extinguishers are on site
- Any soldering to be checked one hour and four hours after completion

### **FIRE CONTROL**

In the event of a small, localized fire, fire extinguisher to be used by General Contractor and/or Fire department must be notified of any fire.

### **FIRE WARNING**

Site foreman is the designated person. Any worker to sound fire alarm in the event of a fire Call 911 fire department, advise job foreman that this has been done

### **SITE EVACUATION**

When a fire alarm is sounded, all workers must leave the site, and gather in a safe location  
Ensure all workers are evacuated from site, but do not put any person in danger to do so.  
Advise fire department of any persons that may be on site

**911 fire department**